

PRASARBHARTI
(BROADCASTING COPROTATION OF INDIA)
ALL INDIA RADIO : BIKANER

BY REGISTERED POST

No Bik 1(2)/2011/METP/IEBR/H.P./E / 206125 2071

Dated : 17-10-2011

M/s.....श्री. श्री. अशोक. शर्मा. (प्रा. रे. बि.)

.....

.....

Subject: Supplying Installation, Testing and Commissioning of 250 KVA Sub-station works at All India Radio, Bikaner (Rajasthan).

Quotation No. Bik.1(2)/2011/METP/IEBR/H.P./E/ dated 17/10/2011

Last date of receipt of quotation in this office : 15-11-2011

Dear Sir,

Please furnish your quotation for the stores mentioned in the enclosed quotation form. Your quotation should fulfill the following conditions: -

- A. Quotation should be sent in an envelope sealed with wax. The envelope should be addressed to the Dy. Director (Engg.), All India Radio, Bikaner (Raj.) Pin - 334001 so as to reach him up to 14:00 Hrs. on or before 15.11.2011. The quotation will be opened on same day at 15:30 Hrs. in presence of those tender or their agents who may choose to attend.

The cover should be super scribed with the following details:-

1. Material for which the tenders are enclosed.
2. Reference to the letter of enquiry.
3. Opening date of quotation.

Quotation received without proper wax sealing may be rejected.

- B. The quotation should specifically and clearly mention the following:


1. The make of the material.
2. The delivery period.
3. Forwarding and freight charges up to destination in Rs.
4. Any other charges in Rs.

Tenders with entries as extra without giving details may be rejected. Any additional charges if claimed after opening the tender will not be admissible.

- C. Sales Tax: The tenderer should quote sales tax separately. They should furnish then sales tax number in their quotation. Tender with sales tax included without giving details may be rejected.
- D. Excise duty: The tendered should furnished the excise duty charged by them separately in clear terms wherever is applicable. Tenders with excise duty included without details may be rejected.

- E. Terms of Payment : 70% payment on receipt of store in good condition. 20% payment after installation, testing and commissioning of store in satisfactory condition. Balance payment of 10% will be paid after guarantee/warranty period of one year. However payment can be released against FDR/Account Payee Demand Draft/Banker's Cheque of equivalent amount in favour of DDO, Chief Engineer (NZ), AIR & DD, New Delhi valid for guarantee period at least.
- F. Sample: The firm should send a sample whenever it is possible. The item quoted should be ISI marked if available.
- G. Validity: Tender should remain open for acceptance for a period of three months from the date of opening.
- H. O/o the Chief Engineer (NZ), AIR & Doordarshan, Jamnagar House, New Delhi reserves the right to accept any quotation not necessary the lowest. Further the said office reserves the right of increasing/decreasing the quantity of the material of tender depending on actual requirements- The unit rate quoted in tender shall be applicable to the quantity for which the order is placed.
- I. The complete technical details required as per our specification should be furnished along with tender. Relevant drawing/photographs may also be sent.
- J. The quotation not fulfilling condition under para A, E & F be summarily rejected without any further reference.
- K. O/o the Chief Engineer (NZ), AIR & Doordarshan, Jamnagar House, New Delhi reserves to himself the right to accept/reject any or all tenders without assigning any reason whatsoever.
- L. The Earnest Money Deposite (EMD) Rs. 9,000/- (Rs. Nine thousand only) should be submitted along with the tender in the form of FDR/Account Payee Demand Draft/Banker's Cheque payable at New Delhi in favour of DDO, Chief Engineer (NZ), AIR & Doordarshan. The offers without earnest money will not be considered and summarily rejected. The Earnest Money deposited by the tenderer shall be forfeited by this Organization If a tenderer, whose tender has been accepted, fails to furnish Security Deposit within 21 (Twenty One) days from the issue of the acceptance offer of the tender. The Earnest Money of unsuccessful bidders will be returned on finalization of the tender. The earnest money of successful bidder will be returned on receipt of security deposit or it may be adjusted in the security deposit if requested by the tenderer.

Yours Sincerely,


(Naresh Prabhakar)
Assistant Engineer
For Dy. Director (Engg.)



PRASAR BHARATI
(BROADCASTING CORPORATION OF INDIA)
ALL INDIA RADIO : BIKANER

QUOTATION FORM

Please read carefully the terms and conditions in the enquiry form attached to the quotation form.

Subject : Supplying Installation, Testing and Commissioning of 250 KVA Sub-station works at All India Radio, Bikaner (Rajasthan).

Quotations No. : Bik.1(2)/2011/METP/IEBR/H.P./E/

Dated : 17-10-2011

Last date of receipt of quotation on this office 15-11-2011 up-to 1400 hrs.

S.No.	Description of works	Qty.	Rate Per Unit	Total Price
1.	Supply and erection of M.S. Gurdur of suitable size approx 30 feet Approved by J.V.V.N.Ltd. including grouting with cement concrete mortar and fabrication H-pole structure with standard steel M.S. Channel of size (100 X 50 X 8 mm) including nut, bolts and clamps etc. painting with red oxide primer than 2 or 3 coats of aluminum paint.	1 Job		
2.	Mounting of following accessories on the existing (installed) H-pole structure and electrically interconnecting with each other, crimping the socket and taping etc. as required. a. 33 KV, G.O. Set horizontal 400 Amp. b. 33 KV, D.O. fuse set vertical 400 Amp. c. Lightning arrester 1 set d. Pin insulator 1 set e. Fabrication and fixing of 33 KV, 3 phase bus bar of aluminum conductor / cable leads on insulator etc. as required.	1 Job		
3.	Supplying and Making Cable end box of HT Cable of XLPE, size 3 X 50 sq. mm Outdoor type – 02 nos. (for feeder pole & G.O. Sets etc.)	1 Job		
4.	Laying and clamping HT Cable 33 KV, XLPE of the size 3 X 50 Sq. mm from state electricity board feeder pole to GO Set at H-Pole structure and from D.O. fuse to H.T. transformer (150 KVA), primary 33 KV side, the cable is to be provided with standard ISI marked like Havells. The 33 KV, HT XLPE cable of size 3 X 50 Sq. mm including digging 100 X 45 mm cable trench direct in ground, approx. length 45 mtr. and laying of the same cable in suitable B grade G.I. pipes of length approx 5 mtr. and covering the cable with bricks and refilling the trench with sand etc and dressing neatly. Complete in all respect.	1 Job		

5.	Supply of HT Cable 33 KV XLPE of the size 3 X 50 Sq. mm approved make (rate should be quoted in per meter length)	40 mtr.		
6.	Installation of 33/0.4 KV transformer on existing plate form with rise the height of existing plate form with suitable cement concrete up to 4 feet height from 1.5 feet and fabrication and grouting of frame required for HT / LT side cable including fixing and connecting 33 KV cable of size 3 X 120 Sq. mm from HT distribution side.	1 Job		
7.	Complete Earthing work for Sub- Station a. G.I. Earth plate of size 2'X2'X6 mm shall be fixed with G.I. stripe, size 25 X 6 mm fixed with G.I. nut bolt and spring washer and riveted etc. b. Digging pit at marked place of size 2'X2'mm and 10 feet deep. c. Providing and fixing G.I. pipe of 75 mm.dia 10 feet length to be use for pouring water after making suitable holes in GI pipes and fabricate in the pit with earth plate and strip as per instruction of site engineers. d. Each earth pit shall be filled with charcoal (100 kg) and salt (30 kg) and refilled of the pit with sand and soil. All the material related to earthing shall be provided by the contractor.	6 Nos.		
8.	Laying of G.I. Earth strip of size 25 X 6 mm directly in ground and make interconnection with various accessories like T/F, LA, GO, Substation, DO as per requirement.	1 Job		
9.	Supplying of 3½ core and 185 Sq. mm LT cable from LT side of Transformer to as per site requirement of main LT panel rate should be quoted in per mtr.	Per Mtr.		

Note :-

- The whole work is to be done as per site requirement under supervision of site engineer.
- Transformer 250 KVA should be provided by deptt.
- The tenderer is advised to visit the site to assess the actual volume of work before quoting rates.
- Testing of Transformer before commissioning if required as per site requirement.
- Rate of LT Cable and HT Cable shall be quoted in per mtr. length.
- Quotation should be sent in an envelope sealed with wax. The envelope should be address to the Dy. Director (Engg.), All India Radio, Bikaner, Rajasthan.

- Excise Duty :**
- Sales Tax / VAT :**
- Forwarding and Transportation Charges :**
(Actual amount should be given)

D. Other charges :-
(Actual amount should be given)

E. Delivery Period :

F. Delivery Terms :

G. Validity : 3 months

H. Payment Terms :- Within 30 days after completion of work.

I. Guarantee / Warranty :- One Year.

J. Declaration :

We declare that all the conditions as given in the enquiry form have been carefully read by us and are acceptable.

TIN NO.:

Signature of the tenderer with seal

Name (in capital)

Full name of the firm.....

Address

.....

.....

Pin Code.....

Telephone No.

Fax No.

E: mail