

Prasar Bharti  
Broadcasting Corporation of India  
Office of the Assistant Engineer (E)  
CCW: AIR, Akashwani Bhawan,  
New Delhi

No:- 6/AE(E)/AKB/NIQ/2010-11/ 247

Dated:- 2/8/10

**NOTICE INVITING QUOTATION**

Sealed "quotation" are invited on behalf of President of India on item rate basis for the item noted below supply/work so as to reach undersigned on or before on 09-08-2010 upto 3.00PM.

The "quotation" shall be opened on the same day at 3.30 P.M.

The "quotation" should be subscribed as "quotation" for  
(\* )..... due on 09-08-2010

(\* ) Name of work : Providing of A/C points in Metadata Section of Doordarshan Archive at Akashwani Bhawan, New Delhi.

S.No	Description of items	Qty	Unit	Rate	Amount
	As per Schedule attached				

**Terms & condition**

1. Time allowed for completion of work 7 Days after issue of work order.
2. Material is required to be supplied as specified make.
3. Agency is requested to quote their rates inclusive of all taxes, packing, forwarding & transportation.
4. The quotations will be issued to competent Agency.
5. The work has to be done as per CPWD Specifications.


**ISSUED TO :**

Assistant Engineer (E)

**Copy to:-**

1. The Superintending Engineer, AIR, NBH, New Delhi for uploading on internet.
2. The Executive Engineer (E)-I, CCW,AIR, New Delhi
3. The JE(E), CCW,AIR, Akashwani Bhawan, New Delhi
4. Notice Board

AE Chakraborty  
2/8

  
Assistant Engineer (E)

Name of work :-

Providing of A/C points in Metadata Section of Doordarshan Archive at Akashwani Bhawan, New Delhi.

S.No	Description of items	Qty	Rate	Unit	Amount
1	Supplying and Laying of 3 x 6 Sq.mm PVC insulated PVC sheathed Aluminium conductor armoured cable of 1.1 KV grade conforming to IS specification on surface / open duct etc. as required.  1) On surface  2) In Open duct	30 Mtr.  8 Mtr.		Meter Meter	
2	Supplying and fixing 8 way double door single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface / recess, complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required. (But without MCB / RCCB/Isolator)	1 No.		Each	
3	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'B' series, miniature circuit breaker suitable for lighting and other loads of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	3 Nos.		Each	
4	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top along with 20 amps 'C' series, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket outlet and complete with connections, testing and commissioning etc. as required.	3 Nos.		Each	
5	Supplying and making end terminations with brass compression gland of 3 x 6 sq.mm PVC Insulated PVC Sheathed Aluminium Conductor cable of 1.1 KV grade i/c providing and fixing of aluminium lugs etc. as required	6 Nos.		Each	
	Total				


  
Assistant Engineer (E)