

Prasar Bharti
Broadcasting Corporation of India
Office of the Assistant Engineer (E)
CCW: AIR, Akashwani Bhawan,
New Delhi

No:- 6/AE(E)/AKB/NIQ/10-11/ 181

Dated:- 29/6/10

NOTICE INVITING QUOTATION

Sealed "quotation" are invited on behalf of President of India on item rate basis for the item noted below supply/work so as to reach undersigned on or before on 07-07-2010 upto 3.00PM & quotation will be issued by this office.

The "quotation" shall be opened on the same day at 3.30 P.M.

The "quotation" should be subscribed as "quotation" for

(*)..... due on 07-07-2010

(*) Name of work :- Providing and fixing of 1 x 14 W TL5 fitting in store room i/c rewinding, overhauling exhaust fan, ceiling fan etc. at New Broadcasting House, New Delhi.

S.No	Description of items	Qty	Rate	Unit	Amount
	As per Schedule attached				

Terms & condition

1. Time allowed for completion of work 15 Days after issue of work order.
2. Material is required to be supplied as specified make.
3. Agency is requested to quote their rates inclusive of all taxes, packing, forwarding & transportation.
4. The quotations will be issued to competent Agency.
5. The work has to be done as per CPWD Specifications.

ISSUED TO :

Assistant Engineer (E)

Copy to:-

1. The Superintending Engineer, AIR, NBH, New Delhi for uploading on internet.
2. The Executive Engineer (E)-I, CCW,AIR, New Delhi
3. The JE(E), CCW,AIR, NBH, New Delhi
4. Notice Board

AE (Chatterjee)

3/7

[Signature]
Assistant Engineer (E)

Name of work :- Providing and fixing of 1 x 14 W TL5 fitting in store room i/c rewinding, overhauling, exhaust fan, ceiling fan etc. at New Broadcasting House, New Delhi.

S.No	Description of items	Qty	Rate	Unit	Amount
1	SITC of 1 x 14 W TL5 light fitting on the existing M.S. channel / ceiling / wall complete with choke, tube, ceiling rose etc. testing as required. (Cat No. TCH 2041 x TLS 14 W / 830)	15 Nos.		Each	
2	SITC of 300 mm sweep, 1400 rpm, 50 Hz, 230 V on the existing window i/c dismantling of existing glass and P/S wooden band / sheet for proper packing i/c testing as required. (Havells / Crompton)	2 Nos.		Each	
3	Supplying and fixing of 20 mm steel conduit along with accessories in surface i/c painting, cutting / wall or welding on channel etc. as required.	60 Nos.		Each	
4	Supplying / Drawing following size of FR PVC insulated copper conductor cable in existing surface conductor etc. as required. a) 3 x 1.5 Sq.mm b) 4 x 1.5 Sq.mm	40 Nos. 20 Nos.		Each Each	
5	Providing and fixing of One way 15 A piano type switch complete with sheet, M.S. Box in recess complete etc. as required.	2 Nos.		Each	
6	Rewinding and overhauling of following winding burnt ceiling fan, wall fan i/c testing etc. as required. a) Ceiling fan 1400 mm b) Wall Bracket fan 400 mm	10 Nos. 4 Nos.		Each Each	
7	Servicing and overhauling of following defective exhaust fan / wall fan / ceiling fan i/c dismantling, reinstallation etc. complete as required. Wall fan 400 mm a) Ceiling fan b) Exhaust fan	2 Nos. 5 Nos. 5 Nos.		Each Each Each	
8	Replacement of following ball bearing in existing ceiling fan / exhaust fan etc. testing as required. a) 6202 b) 6203	5 Nos. 5 Nos.		Each Each	
	Total				


Assistant Engineer (E)