

PRASAR BHARATI
(BROADCASTING CORPORATION OF INDIA)
OFFICE OF THE ASSISTANT ENGINEER (E)
CIVIL CONSTRUCTION WING : ALL INDIA RADIO,
AKASHVANI BHAWAN, NEW DELHI - 110001
Phone No.: 011-23421216
Email:- aeccwkb@gmail.com

No.: 06/AE(E)/NBH/2011-12/ 28

Date: 29/6/11

NOTICE INVITING QUOTATION

Sealed "quotation" are invited on behalf of President of India on item rate basis for the item noted below supply / work so as to reach undersigned on or before on 07-07-2011 upto 3:00 P.M.

The "quotation" shall be opened on the same day at 3:30 P.M.

The "quotation" should be subscribed as "quotation" for

(*)..... due on 07-07-2011


(*) Name of work :- C/o ESD / NSD for AIR at Mahadev Road, New Delhi.
(SH:- Providing and Fixing flood light fittings for cooling tower area at NBH)

S.No.	Description of items	Qty.	Rate	Unit	Amount
1	As per Schedule Attached				
	Total				

Terms & Condition

1. Time allowed 10 Days.
2. Work shall be required to be carried out as per CPWD Specifications.
3. Agency is requested to quote their rates in words and figures.

ISSUED TO :-


Assistant Engineer (E)


Copy to:-

1. The DDG (E), AIR, NBH, New Delhi - with the request for uploading this on website.
2. The Executive Engineer (E)-I, CCW : AIR, Puhspa Bhawan, New Delhi.
3. Notice Board.

Name of Work :- C/o ESD / NSD for AIR at Mahadev Road, New Delhi.
(SH:- Providing and Fixing flood light fittings for cooling tower area at NBH)

S.No.	Description of Item	Qty.	Rate	Unit	Amount
1	SITC of 150 watt MHN TD 150 W flood light fitting complete with control gear box, lamp etc on the existing wall i/c testing etc as required. (Cat No. MWF 230 SK/150/SYM Phillips make)	3 Nos.		Each	
2	Laying & fixing of departmental supply existing 4 x 16 / 2 x 6 sq.mm PVC insulated PVC sheathed aluminum conductor underground armoured cable of 1.1 KV grade conforming to IS specifications in following way etc as required. a) On surface b) In Open duct	145 mtr. 8 mtr.		Metre Metre	
3	Providing and fixing 6 SWG dia GI wire on surface or in recess for loop earthing along with existing cable as required.	296 mtr.		Metre	
4	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. a) 2 x 6 sq.mm b) 4 x 16 sq.mm	3 sets. 6 sets		Set set	
5	Supplying and fixing of weather proof termination box i/c providing and fixing of wooden plank in base of box and 4 ways 4 Nos Bakelite terminal connector of 20 amps rating and supplying and fixing 1 No. 6 amps SPMCB complete on the wall with necessary nut, bolt i/c painting of box with two coats of enamel paint and testing commissioning as required.	3 Nos.		Each	
6	Supplying and fixing SPMCB B series 15 / 16 amp rating 240 volt suitable for lighting load in the existing MCB DB complete with connection, T/C etc. as required	3 Nos.		Each	
7	Supplying and making straight through joint with cast resin compound i/c ferrules and lugs and other jointing materials for 4 x 16 sq.mm PVC insulated PVC sheathed aluminum conductor cable of 1.1 KV grade as required	2 sets		Each	
8	Carriage of 4 x 16 sq.mm / 2 x 6 sq.mm PVC insulated PVC sheathed aluminum conductor armoured cable of 1.1 KV grade from stores to site as required	153 mtrs.		Meter	
	Total				

Note :- 4 x 16 sq.mm (143 mtrs.) cable and 2 x 6 sq.mm (10 mtrs.) cable as above shall be supplied free of cost to contractor for laying / fixing and recovery rate of the same shall be Rs. 400/- per meter and Rs. 250/- per meter respectively.


Assistant Engineer (E)