



**PRASAR BHARATI  
(BROADCASTING CORPORATION OF INDIA)**

**Office of the Assistant Engineer (Elect)/  
Civil Construction Wing, All India Radio,  
Doordarshan complex, Jhalana Doongri,  
Jaipuri - 302004.  
Ph. 0141-2704452**

No: AE(E)/CCW/JPR/NIQ/2011-2012/ 181

Dated:21-07-2011

**SHORT NOTICE INVITING QUOTATION**

Sealed Item rate Quotation are hereby invited by the undersigned for and on behalf of the President of India for the work mentioned below up to 3:00 PM on 27.07.2011 and opened at 3:30 PM on the same day. The schedule of quantity can be obtained during the office hours from the office of undersigned.

**1. Name of Work :- Lowering of Submersible Pumping Set i/c Supplying and fixing HDPE pipe and submersible cable with the existing HDPE pipe and cable at AIR colony Jaipur.**

**1. Estimated Cost:- Rs 10,106=00**

Condition:-

- 1 The work shall be carried out as per CPWD specification.
2. The rates are inclusive of all taxes but excluding service tax which shall be reimbursed on production of documentary evidence.
3. No T & P shall be issued by Department.
- 4 Time allowed for completion of work is 07 Days .

**ASSISTANT ENGINEER (ELECT)  
Asstt. Engineer (Elect.)  
CCW, All India Radio  
Doordarshan Complex, Jhalana  
JAIPUR**

Name of Work :- Lowering of Submersible Pumping Set i/c Supplying and fixing HDPE pipe and submersible cable with the existing HDPE pipe and cable at AIR colony Jaipur.

Sl.	Description of item	Qty.	Rate.	Unit.	Amount. ₹	Remark
1.	Supplying and fixing 10 Mtr long, 50 mm dia HDPE pipe capable of 8 Kg/Sq.cm. pressure including S/F 50 mm dia.(6") G.I. Nipples along with flanges with bolts and welding the same as required duly coupled with pump., testing etc as required.	1 Job		Job		M/R
2.	S/L one number 3 x 2.5 sq mm PVC insulated copper conductor flat submersible cable and jointing the same with existing cable with necessary material as required.( Finolex/ Plaza/ Kalinga Make)	10 Mtr		Mtr		M/R
3.	Lowering of submersible pumping set duly coupled with HDPE pipe with suitable arrangement for lowering the pump in the borewell with S/F 20 mm dia nylon rope (75 Mtr length), testing etc as required.	1 Job		Job.		M/R
	Total					



ASSISTANT ENGINEER (E)  
Asstt. Engineer (E) (C.C.)  
CCW, All India Radio  
Doordarshan Complex, Jhalana  
JAIPUR