

AE (Internet)  
R 95

**PRASAR BHARATI**  
(Broadcasting Corporation of India)  
Office of the Assistant Engineer (E) Project  
CCW, AIR, A-2 Block, Pocket-B, Radio Colon  
Kingsway Camp, Delhi – 110 009

No. 11/AE(E)-II/KWC/TS/NIQ/2011-12/ 370

Dated :- 07.09-2011


**Notice Inviting Quotation**

Sealed Quotations are invited on behalf on President of India on item rate basis for the items/work noted below so as to reach undersigned on or before 14-09-2011 by 3.00 PM. The quotation shall be opened at 3.30 P.M on the same day. The quotation should be subscribed as 'Quotation for "Construction of Metro staff quarters, Phase-I at AIR, Kingsway Camp, Delhi. (SH: Installation of fans, fittings MCB, drawing wires, testing etc. in quarter No. C-7/12,B-2/1, B-2/3 and B-2/4).."' due on 14-09-2011.

| S.No. | Description of Item      | Qty. | Unit | Rate | Amount |
|-------|--------------------------|------|------|------|--------|
|       | As per attached schedule |      |      |      |        |
|       |                          |      |      |      | Total  |


Conditions :-

1. Work will be carried out as per CPWD specification and to the satisfaction of Engineer-in-Charge.
2. Rate should be inclusive of all taxes / VAT etc. nothing extra will be paid on this account.
3. Time of completion is 3 days.
4. Material to be used in the work shall be as per makes specified in schedule of work/ ISI approved.

  
(YOGESH KUMAR)  
Assistant Engineer (E) -II

Copy to:

1. The EE(E)-Project, CCW, AIR Kingsway Camp, Delhi.
2. AE (E)I-Project, CCW, AIR Kingsway Camp, Delhi.
3. The JE(E), CCW, AIR Kingsway Camp, Delhi.
4. Notice Board.
5. S.E., All India Radio, NBH, New Delhi 110001. for uploading the NIQ on All India Radio website please..
6. M/s Sugai Infotech Pvt. Ltd., 6/35, W.E.A. Karo' Bagh, New Delhi, for uploading the NIQ on www.tenderhome.com website.

  
Assistant Engineer (E) -II

Name of Work :- Construction of Metro staff quarters ,Phase-I at AIR, Kingsway Camp, Delhi. (SH: Installation of fans, fittings MCB, drawing wires, testing etc. in quarter No. C-7/12,B-2/1, B-2/3 and B-2/4).

| S. No. | Description of Item  | Qty. |       | Unit  | Rate | Amount |
|--------|--|------|-------|-------|------|--------|
| 1      | Installation, testing and commissioning of prewired fluorescent fitting / CFL fitting of all type complete with all accessories & tube etc. directly on wall including connection with 1.5 sq.mm. FR PVC insulated copper conduit cable etc as required. | 09   | Nos.  | Each  |      |        |
| 2      | Installation, testing and commissioning of ceiling fan including wiring the down rod upto 30 cm with 1.5 sq.mm FR PVC insulated copper conductor cable etc as required.  | 13   | Nos.. | Each  |      |        |
| 3      | Erection of wall bracket / Ceiling fitting of all sizes & shape containing upto 2 Nos. GLS lamp complete with all accessories including connection etc as required.  | 24   | Nos.  | Each  |      |        |
| 4      | Fixing of 32 Amp / 40 Amp DP MCB in existing MCB DB complete with connection, testing and commissioning etc. as required.  | 4    | Nos.  | Each  |      |        |
| 5      | Supplying & fixing of following size of phenolic laminated sheet cover on existing M.S. Box / Junction box / fan box etc. as required.   |      |       |       |      |        |
| a)     | 180 mm x 120 mm  | 2    | Nos.  | Each  |      |        |
| b)     | Round cover for junction box   | 24   | Nos.  | Each  |      |        |
| c)     | 250 mm x 200 mm  | 3    | Nos.  | Nos.  |      |        |
| 6      | Supplying and fixing brass batten holder /Angle holder including connection etc. as required.(Sainico/Antex /I.S.I. approved make)   | 7    | Nos.  | Each  |      |        |
| 7      | Supplying and fixing following piano type switch / socket on the existing switch box / cover including connections etc. as required. (Anchor/Sainico /Antex /I.S.I. approved make)   |      |       |       |      |        |
| a)     | 15 Amp Switch  | 3    | Nos.  | Each  |      |        |
| b)     | 15 Amp Socket outlet   | 3    | Nos.  | Each  |      |        |
| c)     | 5 Amp Switch   | 14   | Nos.  | Each  |      |        |
| d)     | 5 Amp Socket outlet  | 2    | Nos.  | Each  |      |        |
| e)     | 5 Amp 2 way Switch   | 3    | Nos.  | Each  |      |        |
| 9      | Supplying and drawing following size FR PVC insulated copper conductor, single core cable in the existing surface / recessed steel /PVC conduit as required. (Kalinga/Skytone/Havells/I.S.I. approved make)  |      |       |       |      |        |
| a)     | 3x1.5 sq.mm  | 50   | Meter | Meter |      |        |
| b)     | 2x4 sq. mm   | 25   | Meter | Meter |      |        |
| 10     | Supplying and fixing following rating MCB in the existing MCB distribution board including connection,testing etc.as required  |      |       |       |      |        |
| a)     | 40 Amp DP MCB,'B'series (Havells/Action make)  | 1    | Nos.  | Each  |      |        |
| b)     | 6/16 Amp SP MCB,'B'series(Havells/Action make)   | 5    | Nos.  | Each  |      |        |
| 11     | Supplying and installation of step type fan regulator in the existing switch board / sheet cover including cutting the sheet testing and commissioning etc. as required. (Anchor Make)   | 6    | Nos.  | Each  |      |        |

Total Rs.

Signature of contractor