



Executive Engineer (Elect.)
CIVIL CONSTRUCTION WING

PRASAR BHARATI
(BROADCASTING CORPORATION OF INDIA)
Telefax: 2493 6094
Telephone : 2492 1590
Email : ccwelect@rediffmail.com

All India Radio & Doordarshan, Block 7-10, Basement, New Bldg, TV Centre, Worli, Mumbai

No. : EEE/CCW/NIQ/2011-2012/ 730

Dated: 09/9/2011

NOTICE INVITING QUOTATION

Item rate sealed quotations are hereby invited on behalf of the President of India by the undersigned, from the Contractors for following on 16-09-2011 and will opened on same day at 3.30 P.M in the presence of authorized representatives of the questioners present, if any. The undersigned has the right to reject any or all the quotations without assigning any reasons.

Name of Work: Rewiring Old Computer Room in CSU On Second Floor Office Block, AIR, NBH, Mumbai.

<u>Sr.No</u>	<u>Description of Item</u>	<u>Qty</u>	<u>Rate</u>	<u>Unit</u>	<u>Amount</u>
	As per attached schedule				
	Total				

Conditions:

1. No advance payment will be given.
2. Nothing will be paid extra.
3. The time limit for the work is 15 (Fifteen) Days.
4. Rates should be inclusive of all taxes nothing extra shall be paid on any account.
5. The work will be carried out as per CPWD, Specification.

sd/-

EXECUTIVE ENGINEER (ELECT.)
CCW: AIR: MUMBAI

To,
M/s

Copy to:

1. The Superintending Engineer AIR, 6th Floor
NBH, Sansad Marg, New Delhi-110001. For publishing in the website.
2. The Assistant Engineer (Elect.), CCW, AIR, ~~REDACTED~~ MUMBAI
3. The AAO, CCW (E), AIR, Mumbai.
4. Notice Board.
5. Spare copies.


[Signature]
EXECUTIVE ENGINEER (ELECT.)
CCW: AIR: MUMBAI

Schedule of work

Name of work: Re-wiring In Old Computer Room In CSU on Second Floor, Office Block, AIR, NBH, Mumbai.

Sr. No.	Description	Qty	Unit	Rate	Amount
1	Supplying of Decorative Slim Surface Mounted mirror optic luminaires with serrated aluminium cross lovers & white engineering plastic end cap suitable to operate on 230 V, Single Phase, A.C supply complete with accessories like choke, stater, lamp etc. comple (Make - Crompton Cat No- 1x28Watt T5 CS128EB)	11	Each		
2	Installation, testing and commissioning of pre-wired, fluorescent fitting/compact fluorescent fitting of all types, complete with all accessories and tubes etc. directly on ceiling/wall, including connection with 1.5 Sq.mm. FR PVC insulated, copper conductor etc as required.	11	Meter		
3	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FR PVC insulated copper conductor single core cable in surface/recessed PVC conduit as required.				
a	2 x 2.5 Sq.mm. + 1 x 2.5 Sq.mm. earth wire	20	Meter		
b	4 x 2.5 Sq.mm. + 2 x 2.5 Sq.mm. earth wire	20	Meter		
4	Wiring for light/power plug with 2 x 4 Sq.mm. FR PVC insulated copper conductor single core cable in surface/recessed PVC conduit alongwith 1 No 4 Sq.mm. FR PVC insulated copper conductor single core cable etc. as required.	15	Meter		
5	Wiring for light/power plug with 4 x 4 Sq.mm. FR PVC insulated copper conductor single core cable in surface/recessed PVC conduit alongwith 2 Nos 4 Sq.mm. FR PVC insulated copper conductor single core cable etc. as required.	25	Meter		
6	Supplying and drawing following pair 0.5 Sq.mm. FR PVC insulated copper conductor, unarmoured telephone cable in the existing surface/recessed steel/PVC conduit as required.				
a	4 Pair	20	Meter		
7	Supplying and fixing of following sizes of PVC conduit along with accessories in surface/recessed including cutting the wall and making good the same in case of recessed conduit as required				
a	25 mm	15	Meter		

No.	Description	Qty	Unit	Rate	Amount
8	Supplying and fixing following type modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 amps switch	36	Each		
b	15/16 amps switch	12	Each		
c	3 pin 5/6 amps socket outlet	36	Each		
d	6 pin 15/16 amps socket outlet	12	Each		
e	Telephone socket outlet	5	Each		
9	Supplying and fixing following size/modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
a	12 Modular	12	Nos		
b	2 Module	5	Nos		
10	Supplying, installation, testings & commissioning of 300mm sweep heavy duty poly carbonate with built in lowers exhaust fan suitable to operate on 230 V, Single Phase, A.C supply complete with accesseries like louvers etc. complete as required. (Make - GMC)	1	Each		
11	Supplying & Fixing of PVC/Plywood C cannels of Suitable Size to accomodate PVC conduit & electrical Wiring, G.I.Boxes etc lenth including painting the same with shade to match the colour of wall & Wooden partition complete as required.	1	Job		
	Total Rs.				


 Executive Engineer (Elect)
 CCW: AIR: MUMBAI