



**Executive Engineer (Elect.)
CIVIL CONSTRUCTION WING**

PRASAR BHARATI
(BROADCASTING CORPORATION OF INDIA)

Telefax: 2493 6094
Telephone: 2492 1590
Email: ccwelect@rediffmail.com

All India Radio & Doordarshan, Block 7-10, Basement, New Bldg, TV Centre, Worli, Mumbai #
No. : EEE/M/40(11)/2010-11/ 293 Date:-15-06-2010

NOTICE INVITING QUOTATION

Item rate sealed quotations are hereby invited on behalf of the President of India by the undersigned, from the agencies for following work on **25.06.2010** till 3:00 p.m and will be opened on same day at 3.30 p.m in the presence of authorized representatives of the quotationers present, if any. The undersigned has the right to reject any or all the quotation without assigning any reasons.

Name of Work :- Construction of CTI Building at DDK, Worli, Mumbai.(SH- S/I/T/C of Portable fire extinguishers & early Fire Alarm System.

Sr.N	Description of Item	Qty	Rate	Unit	Amount
1)	As per Sheet Attached				
Total					

Conditions:

1. No advance payment will be given.
2. The time limit for the work is 30 (Thirty) Days.
3. The rate should be firm inclusive of all taxes, duties nothing will be paid extra on any amount.
4. Work is to be done per relevant CPWD specifications for Fire Fighting / Fire Alarm works.
5. Security deposit will be deducted at the rate of 10 percent of work done and will be kept for period of six month from the date completion of work.

To,

EXECUTIVE ENGINEER (ELECT.)
CCW: AIR: MUMBAI

Copy to:

1. The Assistant Engineer (Elect.), CCW, AIR, F.D., Mumbai.
2. A.A.O., O/o Executive Engineer (E), CCW, AIR, Mumbai.
3. The Junior Engineer (E), CCW, AIR, Mumbai.
4. Notice Board.
5. The Superintending Engineer, AIR, 6th floor, NBH, Sansad Marg, New Delhi 110011 with the request to upload this quotation at AIR tender website soft copy of NIQ and blank schedule has been send to bhinternet@air.org.in.

EXECUTIVE ENGINEER (ELECT.)
CCW, AIR, Mumbai.

ESTIMATE

Name of Work.:- Construction of CTI Building at DDK, Worli, Mumbai.(SH- S/I/T/C of Portable fire extinguishers & early Fire Alarm System.

S.N	Description of Item	Qty	Unit	Rate	Amount
1	Supplying, Installation, Testing, & Commissioning of addressable single loop panel UL (USA0, VDS (Germany approved suitable for following detectors + modules per loops for 2 loops with 80 character LCD backlit display suitable for operation on 6 AMPS power supply 230 AC input & 24 Volts DC output, the network compatible for peer to peer (optional) 96 nos. of NFPA - 12 compliant CO2 release circuits built in along trouble supervisory release and having qwerty programmable keypad etc as required. (As per NOTIFIER/ ESSER/ HONEYWELL MAKE).	1	Jobs		
2	Supplying, Installation, Testing, & Commissioning of addressable Photo smoke detector with accessories such as detector base with inbuilt isolated module, junction box etc. UL (USA), VDS (Germany) approved and address selection with decade switch etc as required. (As per NOTIFIER/ ESSER/ HONEYWELL MAKE).	40	Jobs		
3	Supplying, Installation, Testing, & Commissioning Response indicators etc. as required.	14	Jobs		
4	Supplying, Installation, Testing, & Commissioning of fault isolator module etc as required. (As per NOTIFIER/ ESSER/ HONEYWELL MAKE).	4	Jobs		
5	Supplying, Installation, Testing, & Commissioning of horn & strobe sounder with relay module for fire alarm UL (USA), VDS (Germany) approved etc as required. (As per NOTIFIER/ ESSER/ HONEYWELL MAKE).	1	Jobs		
6	Supplying, Installation, Testing, & Commissioning of addressable manual call point type pull down station UL (USA), VDS (Germany) approved etc as required. (As per NOTIFIER/ ESSER/ HONEYWELL MAKE).	4	Jobs		
7	Providing & fixing following sizes PVC conduit along with accessories on surface or in recessed including cutting the walls and making good the damages etc as required.				
	(a) 20 mm dia	20	Mtr		
	(b) 25 mm dia	25	Mtr		
9	Supplying & drawing of following sizes of FR PVC insulated single core copper conductor, single core cable in the existing surface/ recessed steel / PVC conduit etc as required.				
	(a) 2 x 1.5 sq. mm.	200	Mtr		
	(b) 4 x 1.5 sq. mm.	20	Mtr		
10	Supply & installation of ABC type dry camical powder fire extingunshar ISI marked as per IS 14839 wall mounting bracket etc. as required of following capacity				
	(a) 10 Kg	2	Each		
	(b) 5 KG	21	Each		

TOTAL

Executive Engineer(E)
CCW, AIR, MUMBAI