

Prasar Bharti
Broadcasting Corporation of India
Civil Construction Wing: All India Radio
Electrical Sub: Division: Nagpur: 440001

NO.AEE/NGP/W-8/2011-12

Dated 13-5-2011

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited on behalf of the President of India for the work mentioned below from the contractors of CPWD/BSNL/MTNL/P&T/MES/Railway/State PWD so as to reach this office on or before 24-5-2011 up to **3.00 p.m.** and the same will be opened on same day at **3.30 p.m.** in the presence of the Contractors or his authorized representatives. The undersigned reserves the right to accept/reject any/all quotations without assigning any reasons.

Name of work:- Provision of Timer for Street Light around old transmitter building at DDK, Nagpur

S.No	Description of item	Quantity	Rate	Unit	Amount
	AS PER SHEDULE ATTACHED				

Total ₹

Issued to:- _____

Terms & Conditions of work:-

1. Work is to be carried out as per CPWD specifications.
2. No T & P will be issued by the Department.
3. Payment shall be made only after completion of work from the office of EE(E),CCW,AIR,Nagpur.
4. Rate quoted should be inclusive of all the taxes like sale tax, VAT, octroi, work contract tax, service tax etc.
5. Time to complete the work will be 15 days from the date of issue of work order.

Assistant Engineer (Elect)

Copy to:-

1. The Executive Engineer (Elect), CCW, AIR, Nagpur.
2. The Assistant Engineer (Civil), CCW, AIR, Nagpur
3. Junior Engineer (Elect) CCW, AIR, Nagpur.
4. Notice Board of Sub-Division Office, CCW, AIR, Nagpur.
5. M/S Sugal infotech Pvt. Ltd., 6/35 W.E.A, Karol Bagh, New Delhi - 110005 for uploading the tender on their website.
6. Superintending Engineer, New Broadcasting House, All India Radio, New Delhi-110001, for uploading the on quotation on AIR website.

SHEDULE OF WORK

Name of work:- Provision of Timer for Street Light at All India Radio, Civil Lines, Nagpur

S.No	Description of Items	Quantity	Unit	Rate	Amount
1	Supplying ,installation,testing and commissioing of metal board of Size 250 mm x 200 mmx150 mm with locking arrangement fabricated from 16 SWG CRCA sheet on the existing wall including connection,interconnection with suitable size copper wire,brass connector strip, earthing etc including supplying & fixing the following accessories on 6mm thick phenolic laminated sheet etc as required. a)Contactor MN 32 (L & T make) -1 No b)Timer Switch J648 F1 (L & T make) -1 No	1	Set	Each	
2)	Supplying and Laying of following Size one number PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.11 kv grade of Size not exceeding 25 sq mm on surface etc as required. a) 2x10 sqmm	3	Mtr	mtr	
3	Supplying and making of end termination with grass compression gland for folloeing size PVC insulated and PVC sheathed XLPE aluminium cable of 1.1KV grade etc as required				
a)	2x10 sqmm	2	Set	Set	

TOTAL

₹

Assistant Engineer (Electrical)