



Phone No. 0755 2660713

e-mail: aeccwairbpl@gmail.com

Prasar Bharati
Broadcasting Corporation of India
Office of Assistant Engineer(Electrical)
Civil Construction Wing: All India Radio
Doordarshan Kendra, Shayamla Hill
Bhopal: 462013

NO.AEE/BPL/CCW/4(5)/2011-12

Dated 18-7-2011

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited on behalf of the President of India for the work mentioned below from the contractors of CPWD/BSNL/MTNL/P&T/MES/Railway/MP State PWD so as to reach this office on or before 28-7-2011 up to **3.00 p.m.** and the same will be opened on same day at **3.30 p.m.** in the presence of the Contractors or his authorized representatives. The undersigned reserves the right to accept/reject any/all quotations without assigning any reasons.

Name of Work: SITC of Open well Mono submersible water pumpset in sumpwell including cubical control panel, Service connection at All India Radio, Bhopal .

S.No	Description of item	Quantity	Rate	Unit	Amount
	AS PER SHEDULE ATTACHED				

Total ₹

Issued to:- _____

Terms & Conditions of work:-

1. Work is to be carried out as per CPWD specifications.
2. No T & P will be issued by the Department.
3. Payment shall be made only after completion of work from the office of EE(E),CCW,AIR,Nagpur.
4. Rate quoted should be inclusive of all the taxes like sale tax, VAT, octroi, work contract tax, service tax etc.
5. Time to complete the work will be One month from the date of issue of work order.

(RAJINDER SINGH)
ASSISTANT ENGINEER (ELECT)

Copy to:-

1. The Executive Engineer (Elect), CCW, AIR, Nagpur.
2. The Executive Engineer (Civil), CCW, AIR, Bhopal
3. The Station Engineer, All India Radio, Bhopal
4. The Assistant Engineer(Civil), CCW, AIR, Bhopal
5. Junior Engineer (Elect) CCW, AIR, Bhopal.
6. Notice Board of Sub-Division Office, CCW, AIR, Bhopal.
7. M/S Sugam infotech Pvt. Ltd., 6/35 W.E.A, Karol Bagh, New Delhi - 110005 for uploading the NIQ on their website.
8. Superintending Engineer, New Broadcasting House, All India Radio, New Delhi-110001 for uploading the NIQ on AIR website.

(RAJINDER SINGH)
ASSISTANT ENGINEER (ELECT)

SHEDULE OF WORK

Name of Work: SITC of Open well Mono submersible water pumpset in sumpwell including cubical control panel, Service connection at All India Radio Bhopal

S.No	Description of item	Quantity	Unit	Rate	Amount
1	SITC of monosub water pumpset capable to deliver 470 ltrs per Minute at a head of 30 mtr having 50mm dia. delivery for operation on 400/440volt 3 phase 50 Hz A.C. supply alongwith 2 nos of 6mm dia GI wire ropes from pumpset to sumpwell surface top and other accessories inside sumpwell i/c connection etc complete as required.(KSB pump+motor monosub Model No. MR 5.0 HH 5 HP or the make as approved by deptt.)	1 Set	Set		
2	S/F of B class ISI marked G.I. Pipe of following sizes with all accesseries like collars, nipples, reducers, tees,bends etc i/c painting with 2 coats of anticorrosive paint and leakproof joints on surface for pumpsets etc as required.(Swastic ISI or the make as approved by deptt.)				
a)	65mm dia	12 M	Meter		
b)	50 mm dia	3 M	Meter		
3	S/F of following sizes ISI make Gun Metal gate valve with leakproof joint etc as required.				
a)	65 mm dia.	1 No.	Each		

S.No	Description of item	Quantity	Unit	Rate	Amount
4	S/F of 65mm dia cast iron flange coupling alongwith two nos of rubber gasket sheets; nut bolts suitable to make joint of 65mm dia G.I. Pipe i/c painting etc as required.	3 Set	Set		
5	S/F M.S. clamp of suitable size for 50/65mm dia G.I. Pipe on the sumpwell i/c nut bolts painting etc as required.	1 Set	Set		
6	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as required.				
a)	2 x 2.5 sqmm (For earthing the pumpset)	40 M	Meter		
7	Reallignment of existing 65mm dia GI pipe water line by dismantling,making necessary holepass in wall or sumpwell,giving supports of brick masonary as and where required,making leakproof joints, painting etc as required.	30 M	Meter		
8	S/L of 3x2.5 sqmm pvc insulated and pvc sheathed copper conductor flat submerssible cable 1.1 kv grade confirming to IS in the existing GI pipe etc as required	40 M	Meter		
9	SITC of Submersible Pump Starter housed in Sheet Enclosure of L&T make Type MUG-6 DOL Starter suitable for 3 phase 440 volt 50 Hz , 5HP submerssible pumpset interconnection including fixing the panel on wall etc complete as required.	1 Set	Set		
10	Supplying and fixing of 25 mm dia. sizes of PVC conduit along with accessories in surface /recess including cutting the wall and making good the same in case of recessed conduit as required	40 M	Meter		

TOTAL ₹

ASSISTANT ENGINEER (ELECT)