

Name of work: Addition & Alteration at SFA, New Delhi  
(SH : SITC of 1.5Tr. cap. split AC in Sound Control Room)

Sl.No.	Description of Items	Qty	Unit	Rate	Amount
1.	SITC of 1.5Tr. cap. (4500 Kcal/Hrs.) Hi-wall mounted split air-conditioner suitable for operation on 220V $\pm 10$ % 50Hz single phase AC supply energy efficient model with 3 star rating (xxx) arrangement with 5 Mtr. Copper pipe i/c S/Fixing angle iron frame stand for outdoor unit etc. complete as required. (Make : Voltas Vertis Plus / Daikin / Carrier)	1 No.	Each		
2	S/Fixing of copper tubing suitable for 1.5Tr. split AC with 12mm thick nitrile rubber insulation etc. as required.	15 Mtr.	Meter		
3	S/Fixing 25mm dia PVC pipe (Heavy Duty) complete with tee, bends etc. on surface/recess for drains etc. as required.	5 Mtr.	Meter		
4	S/Laying / Fixing of 3x4sqmm PVC insulated & PVC sheathed copper Conductor 1.1KV grade cable as confirming to IS-specifications directly on surface / recess / open duct etc. as required.	30 Mtr.	Meter		
5	S/Fixing of 3 module G.I. box with modular plate & cover in front on surface or in recess i/c P/F of twin 25Amp. Socket & 25Amp. SP Tini MCB etc. as required.(ROMA / NORTHWEST Make)	1 No.	Each		

  
10/8/10  
Assistant Engineer (F)  
CCW, All India Radio  
Sirifort Auditorium  
New Delhi