

**PRASAR BHARTI  
BROADCASTING CORPORATION OF INDIA  
O/o ASSISTANT ENGINEER (E)-II, CCW, AIR, 11<sup>th</sup> Floor, SOOCHNA BHAWAN  
NEW DELHI – 110003 Ph :- 011 – 24369919**

No. AE(E) / SB / W-8 / 11-12 /

Dated : 05/9/2011

**SHORT NOTICE INVITING QUOTATION**

Sealed Quotations are invited on behalf of President of India on item Rate basis for the items noted below. Supply/ work so as to reach to undersigned on or before 08-9-2011 by 3.00P.M.

The quotation shall be opened on the same day at 3.30 P.M.  
The quotation should be subscribed as "Quotation" for \* \_\_\_\_\_  
\_\_\_\_\_ Due on 08-9-2011

**Name of work: - Construction of Soochna Bhawan, Ph-V, at New Delhi.  
(SH: Service connection to C & D Block at 10th Floor)**

S.No.	Description of items	Qty.	Rate	Unit	Amount
1.	As per schedule attached				

**CONDITIONS:**

1. The time allowed for completion of work will be 1 week.
2. Agency is requested to quote their rates inclusive of all taxes and nothing extra shall be paid.
3. The work will be carried out as per CPWD Specification.
4. No Govt. T&P will be issued to the agency.


  
Assistant Engineer(E)

Schedule of Work

Name of Work:- C/o Soochna Bhawan Ph-V at New Delhi.

(SH : Service connection to C & D Block at 10th Floor)

S. No.	Description of Item	Qty.	Unit	Rate	Amount
1	Supplying, laying and fixing of one no PVC insulated PVC sheathed Al. Conductor armoured cable conforming to IS: 1554 (Part-1) with upto date amendment on surface/cable tray etc. complete as required & as per direction of Engineer-in-charge.				
(a)	3 1/2 x 50 Sqmm	21 Mtrs.	Mtr.		
(b)	3 1/2 x 35 Sqmm	21 Mtrs.	Mtr.		
2	Supplying and fixing 100 Amp 3 pole MCCB suitable for 415 Volt 50 Hz with 10kA bracking capacity in sheet steel and enclosure fixed on wall i/c connection testing etc complete as required.	1 Jobs	Jobs		
3	Supplying and making end termination with brass compression gland and aluminum lugs for PVC insulated PVC sheathed aluminum conductor armored cable of following sizes.				
(a)	3 1/2 x 50 Sqmm.	2 set	set		
(b)	3 1/2 x 35 Sqmm.	2 set	set		
4	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	42 Mtrs.	Mtr.		

  
NARENDRA PAL  
Assistant Engineer (E) Sub Div.-II  
CCWA All India Radio  
Soochna Bhawan, New Delhi